Declaration of Conformity We, Manufacturer

ZIPPY TECHNOLOGY CORP. 10F,No.50,MIN MINQUAN RD. XINDIAN DIST, NEW TAIPEI CITY TAIWAN, R.O.C.

declare that the product (description of the apparatus, system, installation to which it refers)

SWITCHING POWER SUPPLY P1S-2400V-R

is in conformity with

(reference to the specification under which conformity is declared) in accordance with 2014/30/EU-EMC Directive

■EN 55032 : 2012/AC:2013
Information technology equipment
-Radio disturbance characteristics
-Limits and methods of measurement

■EN 55024 : 2010
Information technology equipment
-Immunity characteristics
-Limits and methods of measurement
■EN 61000-4-2 : 2009 Criteria B
Electrostatic discharge

■EN 61000-4-3: 2006+A1:2008+A2:2010 Criteria A Radiated, radio frequency electromagnetic field

■EN 61000-4-4: 2012 Criteria B Electrical fast transient requirements "EFT"

requirements "ESD"

■EN 61000-4-5 : 2014 Criteria B Surge Immunity requirements

■EN 61000-4-6 : 2014 Criteria A Conducted Immunity

■EN 61000-4-8: 2010 Criteria A Power Frequency Magnetic Field Immunity

Dip Criteria B
Interruptions Criteria C
Voltage Dip,interruptions
Immunity requirements

EN 61000-3-2: 2014 Harmonic current requirements

EN 61000-3-3: 2013 Voltage fluctuations and flicker requirements

Checked by:	ked by: Karen		MAR,08,2017	
_	(Karen Ma / Engineer)	_		
Approved by : _	Jeff Huang / Director)	_ , Date :	MAR,08,2017	

APPLICATION FOR CERTIFICATION ON Behalf Of ZIPPY TECHNOLOGY CORP. SWITCHING POWER SUPPLY

Model#: P1S-2400V-R

PREPARED FOR:

ZIPPY TECHNOLOGY CORP. 10F., No.50, MINQUAN RD., XINDIAN DIST., NEW TAIPEI CITY TAIWAN, R.O.C

REPORT BY:

ZIPPY TECHNOLOGY CORP. 10F., No.50, MINQUAN RD., XINDIAN DIST., NEW TAIPEI CITY TAIWAN, R.O.C

> TEL: (02)2918-8512 FAX: (02)2913-4969

TABLE OF CONTENTS

Description	Page
1. Test Report Certification	. 5
2. General Information	. 6
2.1 Production Description	6
2.2 Tested System Details.	. 7
2.2.1 Resistor Load.	7
2.3 Test Methodology.	7
2.4 Test Facility	. 7
3. Electronic-Magnetic Interference Test	8
3.1. Conducted Power Line Test.	8
3.1.1 Test Equipments	8
3.1.2 Block Diagram of Test Setup.	8
3.1.3 Conducted Powerline Emission Limit	9
3.1.4 EUT Configuration on Measurement	. 9
3.1.5 EUT Exercise Software	. 9
3.1.6 Conducted Emission Data.	. 9
3.2. Radiation Emission Test	. 15
3.2.1 Test Equipment	15
3.2.2 Test Setup	. 15
3.2.3 Radiated Emission Limited	. 16
3.2.4 EUT Configuration	. 17
3.2.5 Operating Condition of EUT	. 17
3.2.6 Radiated Emission Data	. 17
3.2.7 Test Photo and Setup	21
4. ESD Measurement	. 22
4.1 Test Equipments.	. 22
4.2 Test Setup	. 22
4.2.1 Block Diagram of Connections between EUT and simulators	22
4.2.2 Test Setup of EUT.	. 22
4.3 Severity Levels	. 23
4.4 EUT Operating Condition	. 23
4.5 Test Procedure	. 23
4.6 Test Method.	23
17 Test Result	24

TABLE OF CONTENTS

Description	Page
5. Radiated Susceptibility Measurement	25
5.1 Test Equipment	25
5.2 Block Diagram of Test Setup.	25
5.3 Severity Levels	26
5.4 EUT Operating Condition	26
5.5 Test procedure	26
5.6 Test Method.	26
5.7 Test Result.	27
6.Electrical Fast Transient/Burst Measurement	28
6.1 Test Equipment	28
6.2 Block Diagram of Test Setup.	28
6.3 Severity Levels	28
6.4 EUT Operating Condition	29
6.5 Test procedure	29
6.6 Test Method	29
6.7 Test Result.	30
7. Harmonic Current Requirements	31
8. Voltage Fluctuation and Filcker Test	33
9. Surge Immunity Test	34
10. Conducted Immunity Test	35
11. Voltage Dip,interruptions Immunity Test	36
12. Power Frequency Magnetic Field (PFM) Immunity Test	37
13. Photographs	38
14. EMI Reduction method during compliance Testing	41

1. Test Report Certification

Applicant : ZIPPY TECHNOLOGY CORP.

Manufacturer : ZIPPY TECHNOLOGY CORP.

EUT Description : Switching Power Supply

(A) Model No. : **P1S-2400V-R**

(B) Serial No. : N/A

(C) Power Supply : 115Vac/60Hz,230Vac/50Hz

MEASUREMENT PROCEDURE USED:

EN 55024 RULES EN 55032 RULES

THE DEVICE DESCRIBED ABOVE WAS TESTED BY ZIPPY SHIN JIUH CORP. TO DETERMINE THE SEVERITY LEVELS THE DEVICE CAN ENDURE AND ITS PERFORMANCE CRITERION.

THE MEASUREMENT RESULTS ARE CONTAINED IN THIS TEST REPORT AND ZIPPY SHIN JIUH CORP. IS ASSUMED FULL RESPONSIBILITY FOR THE ACCURACY AND COMPLETENESS OF THESE MEASUREMENT. ALSO, THIS REPORT SHOWS THAT THE EUT TO BE TECHNICALLY COMPLIANT WITH THE EN STANDARD.

2. General Information

2.1 Production Description

Description : Switching Power Supply

Model Number : P1S-2400V-R

Applicant : ZIPPY TECHNOLOGY CORP.

Address : 10F., No.50, MINQUAN RD., XINDIAN DIST.,

· NEW TAIPEI CITY TAIWAN, R.O.C

Data Cable : N/A

PowerCord : Non-Shielded, detachable, 1.5m

2.2 Tested System Details

The FCC IDs for all equipment, plus descriptions of all cables used in the tested system (including inserted cards, which have grants) are:

2.2.1 Resistor Load

Model Number : ELECTRONIC LOAD

Serial Number : N/A

Manufacturer : ZIPPY

Power : 400W

2.3 Test Methodology

EMI Test:

Both conducted and radiated testing were performed according to the procedures in EN 55032 Radiated testing was performed at an antenna to EUT distance of 10 meters.

EMS Test:

Performed according to procedures in EN 61000 series regulations.

2.4 Test Facility

ZIPPY TECHNOLOGY CORP. 10F., No.50, MINQUAN RD., XINDIAN DIST., NEW TAIPEI CITY TAIWAN, R.O.C

3. Electronic-Magnetic Interference Test


3.1 Conducted Power Line Test

3.1.1 TEST Equipment's

The following test equipment's are used during the conducted power line tests:

Item	Instrument	Manufacture	Type No:	Last Calibration
1	TEST RECEIVER	ROHDE & SCHWARZ	ESL	Mar.,2017
2	LISN	ROHDE & SCHWARZ	ENV4200	Dec.,2016
2		ROHDE & SCHWARZ	ENV216	Apr.,2016
3	SHIELDE	N/A		

3.1.2 Block Diagram of Test Setup



3.1.3 Conducted Powerline Emission Limit

Maximum RF Line Voltage dB(uV)						
Frequency	Class A					
MHz	QUASI-PEAK	AVERAGE				
0.15 - 0.50	79	66				
0.50 - 5.0	73	60				
5.0 - 30	73	60				

Remarks: In the Above Table, the tighter limit applies at the band edges.

3.1.4 EUT Configuration on Measurement

The equipment's which is listed 3.2 are installed on Conducted Power Line Test to meet the Commission requirement and operating in a manner which tends to maximize its emission characteristics in a normal application.

3.1.5 EUT Exercise Software

The EUT exercise program used during conducted testing was designed to exercise the EUT in a manner similar to a typical use. The exercise sequence is listed as below:

- 3.1.5.1 Setup the EUT and simulators as shown on 3.2.
- 3.1.5.2 Turn on the power of all equipment's.

3.1.6 Conducted Emission Data

The measurement range of conducted emission which is from 0.15 MHz to 30 MHz was investigated. The initial step in collecting conducted data is a spectrum analyzer peak scan of the measurement range for all the test modes. Then the worst modes were reported the following data pages.

Conducted Emission Data

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : **P1S-2400V-R** HUMIDITY : 65%

Frequency	Reading L	evel dBuV	Limites
MHz	Line 1	Line 2	DBuV
15.70	57.95	56.87	73.00
16.55	56.07	54.96	73.00

Remark: All readings are Quasi-Peak values.

REPORT NO.: 17030807

ZIPPY EMC LAB

conduction test

EUT: P1S-2400V-R SPS
Manuf: ZIPPY TECH CO..LTD

Op Cond: FULL LOAD

Operator:

Test Spec: EN 55032-- Class A Comment: Load Condition

L220V

Scan Settings	(3 Ranges)									
Frequencies ————			1	Receiver Settings —						
Start	Stop	Step	IF BW	Detector	M-Time	Atten	Preamp	OpRge		
150kHz	500kHz	2kHz	10kHz	QP+AV	50msec	Auto	OFF	60dB		
500kHz	5MHz	20kHz	10kHz	QP+AV	1msec	Auto	OFF	60dB		
5MHz	30MHz	50kHz	10kHz	QP+AV	1msec	Auto	OFF	60dB		


 Transducer
 No.
 Start
 Stop
 Name

 1
 9kHz
 30MHz
 CEB

Prescan Measurement: Detectors: X QP / + AV

Meas Time: see scan settings

Peaks: 8 Acc Margin: 25 dB



ZIPPY EMC LAB

conduction test

EUT: P1S-2400V-R SPS Manuf: ZIPPY TECH CO..LTD

Op Cond: FULL LOAD

Operator:

Test Spec: EN 55032-- Class A Comment: Load Condition

L220V

Scan Settings	(3 Rar —— Frequen					Receiver Se	ettings —		
Start 150kHz 500kHz 5MHz	Stop 500kHz 5MHz 30MHz		Step 2kHz 20kHz 50kHz	IF BW 10kHz 10kHz 10kHz	Detector QP+AV QP+AV QP+AV	M-Time 50msec 1msec 1msec	Atten Auto Auto Auto	Preamp OFF OFF OFF	OpRge 60dB 60dB 60dB
Transducer	No.	Start	Stop		Name				
	1	9kHz	3	30MHz	CEB				
Prescan Meas Peak Search F		Detectors: Meas Time: Peaks: Acc Margin:		P / + AV scan settings IB					
Frequency	QP Level	QP Lin	nit (QP Delta	Phase	PE			
MHz	dΒμV	dΒμV	d	IB	-	-			
15.7	57.95	73.00	1	15.05	N	gnd			
15.8	57.39	73.00	1	15.61	N	gnd			
15.9	56.47	73.00	1	16.53	N	gnd			
16.0	55.58	73.00	1	17.42	N	gnd			
16.1	56.23	73.00	1	16.77	N	gnd			
16.35	56.47	73.00	1	16.53	N	gnd			
16.45	56.89	73.00	1	16.11	N	gnd			

Frequency	AV Level	AV Limit	AV Delta	Phase	PE
MHz	dΒμV	dΒμV	dB	-	-
13.8	49.01	60.00	10.99	N	gnd
14.3	49.13	60.00	10.87	N	gnd
15.05	48.52	60.00	11.48	N	gnd
15.7	48.41	60.00	11.59	N	gnd
15.8	49.50	60.00	10.50	N	gnd
16.45	54.20	60.00	5.80	N	gnd
16.55	49.15	60.00	10.85	N	gnd
17.2	48.01	60.00	11.99	N	gnd

16.93

Ν

gnd

73.00

16.55

56.07

Indicated Phase/PE shows Configuration of max. Emission

^{*} limit exceeded

REPORT NO.: 17030807

ZIPPY EMC LAB

conduction test

EUT: P1S-2400V-R SPS
Manuf: ZIPPY TECH CO..LTD

Op Cond: FULL LOAD

Operator:

Test Spec: EN 55032-- Class A Comment: Load Condition

N220V

Scan Settings	(3 Ra	nges)							
	— Frequei	ncies —		1		Receiver Se	ttings —		
Start	Stop		Step	IF BW	Detector	M-Time	Atten	Preamp	OpRge
150kHz	500kH	Z	2kHz	10kHz	QP+AV	50msec	Auto	OFF	60dB
500kHz	5MHz		20kHz	10kHz	QP+AV	1msec	Auto	OFF	60dB
5MHz	30MHz	!	50kHz	10kHz	QP+AV	1msec	Auto	OFF	60dB
Transducer	No.	Start	Stop		Name				

CEB


30MHz

Prescan Measurement: Detectors: X QP / + AV

9kHz

Meas Time: see scan settings

Peaks: 8 Acc Margin: 25 dB



ZIPPY EMC LAB

conduction test

EUT: P1S-2400V-R SPS ZIPPY TECH CO..LTD Manuf:

Op Cond: FULL LOAD

Operator:

EN 55032-- Class A Test Spec: Load Condition Comment:

N220V

Scan Settings	(3 Ranges)
	F

	Frequencies				Receiver Se	ttings —		
Start	Stop	Step	' IF BW	Detector	M-Time	Atten	Preamp	OpRge
150kHz	500kHz	2kHz	10kHz	QP+AV	50msec	Auto	OFF	60dB
500kHz	5MHz	20kHz	10kHz	QP+AV	1msec	Auto	OFF	60dB
5MHz	30MHz	50kHz	10kHz	QP+AV	1msec	Auto	OFF	60dB

Transducer No. Stop Name 30MHz 9kHz CEB

1

Detectors: X QP / + AV Meas Time: see scan settings

Peaks: 8 Acc Margin: 25 dB

Peak Search Results

Prescan Measurement:

Frequency	QP Level	QP Limit	QP Delta	Phase	PE
MHz	dΒμV	dΒμV	dB	-	-
13.9	54.77	73.00	18.23	N	gnd
15.4	55.58	73.00	17.42	N	gnd
15.5	55.30	73.00	17.70	N	gnd
15.7	56.87	73.00	16.13	N	gnd
16.05	56.67	73.00	16.33	N	gnd
16.15	56.21	73.00	16.79	N	gnd
16.25	57.05	73.00	15.95	N	gnd
16.55	54.96	73.00	18.04	N	gnd
Frequency	AV Level	AV Limit	AV Delta	Phase	PE
MHz	dΒμV	dΒμV	dB	-	-
12.9	47.27	60.00	12.73	N	gnd
13.55					
10.00	47.56	60.00	12.44	N	gnd
15.05	47.56 49.76	60.00 60.00	12.44 10.24	N N	gnd gnd
15.05	49.76	60.00	10.24	N	gnd
15.05 15.5	49.76 48.69	60.00 60.00	10.24 11.31	N N	gnd gnd
15.05 15.5 15.7	49.76 48.69 50.77	60.00 60.00 60.00	10.24 11.31 9.23	N N N	gnd gnd gnd

Indicated Phase/PE shows Configuration of max. Emission

^{*} limit exceeded

3.2 Radiation Emission Test


3.2.1 Test Equipment

The following test equipment's are used during the radiated emission test:

Instrument	Manufacture	Type No:	Last Calibration
Spectrum Analyzer	H.P	8594A	May.,2016
Test Receiver	IFR System	A-7550	Jun.,2016
Preamplifier	H.P	8447D	May.,2016
Biconical Ant.	Emco	3110	Jun.,2016
Log-Periodic Ant.	Emco	3146	Jun.,2016
Dipole Antenna	Emco	3121C	May.,2016

3.2.2 Test Setup

3.2.2.1 Block Diagram of Connection between EUT and simulators




EUT: SWITCHING POWER SUPPLY

3.2.2.2 Open Field Test Site - description

The open field test site (OFTS) is designed to provide an environment in which repeatable tests of radiated emissions can be carried out.

It consists of a flat elliptical area as shown in the diagram below.

The equipment under test and the antenna are placed at the foci of the ellipse.



The antenna height should be remotely adjustable from 1m to 4m. Measuring instrumentation should be outside the ellipse at the position shown or in a room under the ground plane. The whole or part of the site may be enclosed in an RF transparent building. For precompliance testing a 3m test site with a fixed height antenna (at 1.5-2m height) and no metallic ground plane may be used. This may be a clear area on a car park or a grass area but should

3.2.3 Radiated Emission Limit

be away from large metallic structures.

Class A Limits

Frequency	Distance	Field Strength
MHz	Meter	DB(uV/M)
30-230	10	40
230-1000	10	47

Remarks:

- 1. The tighter limit shall apply at the edge between two frequency bands.
- 2. Distance refers to the distance in meters between the measuring instrumentantenna and the closed point of any part of the device or system.

3.2.4 EUT Configuration

The equipment's which is listed 4.2.1 are installed on Radiated Emission Test to meet the Commission requirement and operating in a manner which tends to maximize its emission characteristics in a normal application.

3.2.5 Operation Condition of EUT

Same as Conducted Power Line Test which is listed in 3.1.5.

3.2.6 Radiated Emission Data

The measurement range of radiated emission which is from 30 MHz to 1000 MHz was investigated. The initial step in collecting conducted data is a spectrum analyzer peak scan of the measurement range for all the test modes. Then the worst modes were reported the following data pages.

Radiated Emission Data

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : P1S-2400V-R HUMIDITY : 57%

Г	Emission Level	Lindia	
Frequency	Horizontal	Limits	Remark
(MHz)	dBuV/m	dBuV/m	
82.38	20.04	40.00	
159.98	15.40	40.00	
260.86	28.66	47.00	
493.66	20.23	47.00	
580.96	25.62	47.00	
709.00	25.04	47.00	
870.02	26.26	47.00	


Radiated Emission Data

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C


TEST MODE : **P1S-2400V-R** HUMIDITY : 57%

Frequency	Emission Level	Limits	
Trequency	Vertical	Zimes	Remark
(MHz)	dBuV/m	dBuV/m	
82.38	30.25	40.00	
169.68	24.79	40.00	
270.56	29.87	47.00	
357.86	20.86	47.00	
414.12	23.99	47.00	
540.22	22.24	47.00	
774.96	25.95	47.00	

Horizontal Curve



Vertical Curve



3.2.7 Test Photo and Setup



*During the radiated test, the power-supply has to test with chassis, which is not allowed to be operated stand-alone. (For user, final assembly has to comply with corresponding EMC-and safety-regulations.)

4. ESD Measurement


4.1 Test Equipment

The following test equipment's are used during the ESD test:


Instrument	Manufacture	Type No:	Last Calibration
ESD Simulator system	Keytek	MZ-15/EC	May.,2016
Electronic Load	D-RAM	Load-2000	N/A

4.2 Test Setup

4.2.1 Block Diagram of Connections between EUT and simulators



4.2.2 Test Setup of EUT



4.3 Severity Levels

LEVEL	TEST VOLTAGE CONTACT DISCHARGE	TEST VOLTAGE AIR DISCHARGE
1	2KV	2KV
2	4KV	4KV
3	6KV	6KV
4	8KV	8KV
X	SPECIAL	SPECIAL

4.4 EUT Operating Condition

- 1. Setup the EUT and Test Equipment as shown on 4.2
- 2. power on.

4.5 Test Procedure

Air Discharge:

This test was done above a non-conductive surfaces. The round discharge electrode about 30cm away will approach as fast as possible to touch test points of the EUT.

Discharge happens before the contact. This procedure is repeated ten times on one selected location.

4.6 Test Method

According to IEC 61000-4-2

4.7 Test Result

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : P1S-2400V-R HUMIDITY : 65%

Item	Amount of discharge	Voltage	Results
Contact discharge	500	+2KV -2KV	Pass Pass
Contact discharge	500	+4KV -4KV	Pass Pass
Air discharge	500	+2KV -2KV	Pass Pass
Air discharge	500	+4KV -4KV	Pass Pass
Air discharge	500	+6KV -6KV	Pass Pass
Air discharge	500	+8KV -8KV	Pass Pass

%Input Voltage / Frequency : 230Vac/50Hz


5. Radiated Susceptibility Measurement

5.1 Test Equipment

The following test equipment's are used during the RS test:

Instrument	Manufacture	Type No:	Last Calibration
Signal generator	H.P	8657A	Dec.,2016
Power amplifier	A&R	100A100	Dec.,2016
Field strength meter	A&R	FM2000	Oct.,2016
Field strength sensor	A&R	EP2000	Oct.,2016
Power antenna	A&R	AT1080	Oct.,2016

5.2 Block Diagram of Test Setup



Antennas-layout

For the upper frequency range of 200 to 1000 MHz, antennas are the normal method of producing the required field strength. This is also carried out in an anechoic chamber or a screened room. If a screened room is used it must be damped. The anechoic chamber should be used for compliance testing, the screened room may be used for precompliance testing. The fields in the screened room will not be as uniform as those obtainable in an anechoic chamber and will also not be as repeatable. The EUT is placed on a non-conductive table, 0.8 m above the reference ground plane, which in many cases will be the floor of a screened room. According to the standards, the EUT should be oriented so that its most sensitive side is facing the antenna. In practice it can be difficult to decide beforehand which is the most sensitive side, and in most cases, a series of tests will be required with the EUT in several orientations.

5.3 Severity Levels

LEVEL	FIELD STRENGTH V/M
1	1
2	3
3	10
X	SPECIAL

5.4 EUT Operating Condition

Same as section 4.4.

5.5 Test Procedure

The EUT and load are placed on a table which is 0.8 meter above ground. The field sensor is also placed on the same table to monitor field strength from transmitting antenna.

EUT is set 1 meter away from the transmitting antenna which is mounted on an antenna each time.

The antenna is fixed 1 meter above ground. Both horizontal and vertical polarization of the antenna are set on measurement. In order to judge the EUT performance, a CCD camera is used to monitor EUT screen.

All the scanning conditions are as follows:

Condition of Test

Remarks

1. Field Strength

2. Radiated Signal

3. Scanning Frequency

80 MHz-1 GHz

3. Scanning Frequency4. Sweep Time of Radiated50 MHz-1 GHz60 0.0015 Decade/s

5.6 Test Method

According to IEC 61000-4-3

5.7 Test Result

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : **P1S-2400V-R** HUMIDITY : 65%

Frequency Range (MHz)	Position (Angle)	Polarity (HorV)	Field Strength (V/M)	Results
80-1000	0° (Front)	Н	3	Pass
80-1000	90° (Right)	Н	3	Pass
80-1000	180° (Back)	Н	3	Pass
80-1000	270° (Left)	Н	3	Pass
80-1000	0° (Front)	V	3	Pass
80-1000	90° (Right)	V	3	Pass
80-1000	180° (Back)	V	3	Pass
80-1000	270° (Left)	V	3	Pass

Test Result: Criteria A


6. Electrical Fast Transient / Burst Measurement

6.1 Test Equipment

The following test equipment's are used during the EFT tests:

Instrument	Manufacturer	Type No.	Last Calibration
Fast Transient / Burst enerator	Keytek	EMCpro	May.,2016

6.2 Block Diagram of Test Setup



6.3 Severity Levels

	Open Circuit Output Test Voltage ±10%					
Level	On power supply lines					
1	0.5KV					
2	1KV					
3	2KV					
4	4KV					
X	SPECIAL					

6.4 EUT Operation Condition

Same as section 4.4.

6.5 Test Procedure

The EUT and its load are placed on a table which is 0.8 meter above a metal ground plane measured 1m*1m min. And 0.65 mm thick min. And projected beyond the EUT by at least 0.1m on all sides.

The EUT is away from the walls of the test AC power line test is as follows:

For Ac power line test:

The EUT is connected to the power mains through a coupling device that directly couples the EFT interference signal.

Each of the Line and Neutral conductor is impressed with burst noise for 1 min.

6.6 Test Method

According to IEC 61000-4-4.

6.7 Test Result

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : **P1S-2400V-R** HUMIDITY : 65%

Inject Line	Voltage KV	Frequency (KHz)	Inject time (sec)	Inject Method	Result
L1	±1	5	60	Direct	Pass
L2	±1	5	60	Direct	Pass
PE	±1	5	60	Direct	Pass
L1-L2	±1	5	60	Direct	Pass
L1-PE	±1	5	60	Direct	Pass
L2-PE	±1	5	60	Direct	Pass
L1,L2-PE	±1	5	60	Direct	Pass

**Input Voltage / Frequency : 230Vac/50Hz

7. Harmonic Current Test

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C


TEST MODE : **P1S-2400V-R** HUMIDITY : 65%

Itare	Reading	Leve A	Thomas	Readin	Reading Leve A		
Item	A	Limites	Item	A	Limites		
1	1.9937						
3	0.1037	1.5446					
5	0.1081	0.8632					
7	0.0709	0.4543					
9	0.0527	0.2271					
11	0.0415	0.1590					
13	0.0344	0.1346					
15	0.0298	0.1166					
17	0.0263	0.1029					
19	0.0237	0.0921					
21	0.0218	0.0833					
23	0.0201	0.0760					
25	0.0181	0.0700					
27	0.0167	0.0648					
29	0.0155	0.0603					
31	0.0146	0.0564					
33	0.0137	0.0530					
35	0.0131	0.0500					
37	0.0124	0.0473					
39	0.0119	0.0448					

MODEL: P1S-2400V-R

hroma

ANALYZER 6630



45

Ch	roma	Ī		ANAL	YZER 6630	3			
Current Harmonics Setup: CLASS_D Gen setting: 1(1) U: 230.06 V fu: 50.000 Hz								Next measure	
Live Module:	M1	Limi Note	Analysed periods: 4 I : 2.0034 A P: 454.3 W Limit: Class D (User def) I1: 1.9937 A Note: THD=9.76 % (PF=0.986) PASSED						
No	A	Lim A	No	A	Lim A	No	A	Lim A	Relative current
1	1.9937		15	0.0298	0.1166	29	0.0155	0.0603	
2	0.0002		16	0.0000		30	0.0000		
3	0.1037	1.5446	17	0.0263	0.1029	31	0.0146	0.0564	
4	0.0003		18	0.0000		32	0.0001		
5	0.1081	0.8632	19	0.0237	0.0921	33	0.0137	0.0530	
6	0.0003		20	0.0000		34	0.0000		Write to
7	0.0709	0.4543	21	0.0218	0.0833	35	0.0131	0.0500	disk
8	0.0001		22	0.0001	0.0000	36	0.0002	0.0450	
9	0.0527	0.2271	23	0.0201	0.0760	37	0.0124	0.0473	
10	0.0001	0.4500	24	0.0000	0.0000	38	0.0001	0.0440	
11	0.0415	0.1590	25	0.0181	0.0700	39	0.0119	0.0448	
12	0.0000	0.4346	26	0.0001	0.0640	40	0.0000		1
13	0.0344	0.1346	27	0.0167	0.0648				
14 Current	0.0000 range:	3 Ар	28	0.0001					

Appl: EUROPE

(1212_03)

8. Voltage Fluctuation And Flicker Test

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26°C

TEST MODE : **P1S-2400V-R** HUMIDITY : 65%

		T	1
Item	Reading	Limit	Result
Pst	0.000	1.00	Pass
P1t	0.000	0.65	Pass
Dc (%)	0.000	3.00	Pass
Dmax (%)	0.000	4.00	Pass
Dt (%)	0.000	0.20	Pass

9. Surge Immunity Test

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : **P1S-2400V-R** HUMIDITY : 65%

Waveform	Voltage	Output:LC	Phs Ref	Phs Ang	Tests	Delay	Result
12 Ohm	-2000V	MAINS:L1/PE	L1	0 deg.	5	60 sec	Pass
12 Ohm	-2000V	MAINS:L1/PE	L1	90 deg.	5	60 sec	Pass
12 Ohm	-2000V	MAINS:L1/PE	L1	270 deg.	5	60 sec	Pass
12 Ohm	2000V	MAINS:L1/PE	L1	0 deg.	5	60 sec	Pass
12 Ohm	2000V	MAINS:L1/PE	L1	90 deg.	5	60 sec	Pass
12 Ohm	2000V	MAINS:L1/PE	L1	270 deg.	5	60 sec	Pass
12 Ohm	-2000V	MAINS:L2/PE	L1	0 deg.	5	60 sec	Pass
12 Ohm	-2000V	MAINS:L2/PE	L1	90 deg.	5	60 sec	Pass
12 Ohm	-2000V	MAINS:L2/PE	L1	270 deg.	5	60 sec	Pass
12 Ohm	2000V	MAINS:L2/PE	L1	0 deg.	5	60 sec	Pass
12 Ohm	2000V	MAINS:L2/PE	L1	90 deg.	5	60 sec	Pass
12 Ohm	2000V	MAINS:L2/PE	L1	270 deg.	5	60 sec	Pass
2 Ohm	-1000V	MAINS:L1/L2	L1	0 deg.	5	60 sec	Pass
2 Ohm	-1000V	MAINS:L1/L2	L1	90 deg.	5	60 sec	Pass
2 Ohm	-1000V	MAINS:L1/L2	L1	270 deg.	5	60 sec	Pass
2 Ohm	1000V	MAINS:L1/L2	L1	0 deg.	5	60 sec	Pass
2 Ohm	1000V	MAINS:L1/L2	L1	90 deg.	5	60 sec	Pass
2 Ohm	1000V	MAINS:L1/L2	L1	270 deg.	5	60 sec	Pass

10. Conducted Immunity Test

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : P1S-2400V-R HUMIDITY : 65%

Test frequency Range: 150kHz ~ 80MHz

Frequency Step: 1% of the momentary frequency Dwell Time: Minimum 3 sec. per frequency

Modulation: 1kHz Sine Wave with 80% Amplitude Modulation

Frequency	Polarity	Field Strength	Perfor	mance	Result
Range (MHz)	(HorV)	(V/M)	Required	Observation	Result
0.15-80	Н	3	A	A	Pass

11. Voltage Dip, Interruptions Immiunity Test

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26° C

TEST MODE : P1S-2400V-R HUMIDITY : 65%

Test	Phase	Reduction	Duration	Perfor	mance	D 1.
Voltage	Angle	%	(Periods)	Required	Observation	Result
	0 deg.		0.5	В	A	Pass
	90 deg.	. 0.70/	0.5	В	A	Pass
	180 deg.	>95%	0.5	В	A	Pass
	270 deg.		0.5	В	A	Pass
	0 deg.		25	С	C	Pass
AC 115V	90 deg.	30%	25	С	C	Pass
AC 115V	180 deg.	30%	25	С	C	Pass
	270 deg.		25	С	C	Pass
	0 deg.	4	250	С	С	Pass
	90 deg.		250	С	С	Pass
	180 deg.		250	С	С	Pass
	270 deg.		250	С	С	Pass
	0 deg.		0.5	В	A	Pass
	90 deg.	>95%	0.5	В	A	Pass
	180 deg.		0.5	В	A	Pass
	270 deg.		0.5	В	A	Pass
	0 deg.		25	С	A	Pass
A C 220V	90 deg.	200/	25	С	A	Pass
AC 230V	180 deg.	30%	25	С	A	Pass
	270 deg.		25	С	A	Pass
	0 deg.		250	С	С	Pass
	90 deg.	. 050/	250	С	С	Pass
	180 deg.	>95%	250	С	С	Pass
	270 deg.		250	С	С	Pass

12. Power Frequency Magnetic Field (PFM) Immunity Test

EUT : SWITCH POWER SUPPLY TEMPERATURE : 26°C

TEST MODE : P1S-2400V-R HUMIDITY : 65%

Magnetic Field	Magnetic Field	Perfor	Result	
Orientation	(A/m)	Required	Observation	(Pass/Fail)
X-axis	1A	A	A	Pass
Y-axis	1A	A	A	Pass
Z-axis	1A	A	A	Pass


13. Photographs1. Front view of Power Supply

2.Back view of Power Supply



- 3.Component side of Mainboard
- 4.Solder side of Mainboard





- 5. Inside view of Power Supply
- 6. Inside view of Power Supply





14. EMI Reduction Method During Compliance Testing

1.No modification was made during test.